#### SHUTTLE CRITICAL ITEMS LIST - ORBITER

SUBSYSTEM : CREW MODULE SEALS FMEA NO 01-4 -CS1 -1 REV: 03/29/8

ASSEMBLY : WINDOW ASSEMBLY (FLT DECK OVERHEAD, CRIT. FUNC: 1

FLT DECK AFT, FLT DECK FORWARD)

CRIT. HDW:

:V070-331115, V070-331106 P/N RI

:V070-331555, V070-331705

VEHICLE: 102 103 104 P/N VENDOR:

EFFECTIVITY: QUANTITY :16 V070-331115 Х X Х PHASE(S): PL LO X OO X DO X L : 8 V070-331106

: 8 V070-331555

: 8 V070-331705

REDUNDANCY SCREEN: A-FAIL B-FAIL C-PAS

PREPARED BY:

APPROVED BY:

DES THE Menery 1/21/04 SSM (\* 1) STATE 2-2

REL D.M. Mayne 10 the benefit REL 10 - Robit & 400 & 612

QE TES JUMBER 7/25 REL QE MISSER 3/14/33 DES W. HENRY D. MAYNE REL QE W. SMITH

ITEM:

SEALS, WINDOW PANE ASSEMBLY

FUNCTION:

THESE SEALS PREVENT LEAKAGE OF CREW MODULE ATMOSPHERE.

FAILURE MODE:

LEAKAGE

CAUSE(S):

CRACKS, LOW TEMPERATURE, MATERIAL DEGRADATION

EFFECT(S) ON:

- (A) SUBSYSTEM (B) INTERFACES (C) MISSION (D) CREW/VEHICLE
- (A) FAILURE OF SINGLE SEAL HAS NO EFFECT. FAILURE OF THE REDUNDANT (SPACER/RETAINER) SEAL WOULD RESULT IN THE LOSS OF CREW MODULE CONSUMABLES.
- (B) FAILURE OF SINGLE SEAL HAS NO EFFECT. FAILURE OF THE REDUNDANT (SPACER/RETAINER) SEAL WOULD RESULT IN THE LOSS OF CREW MODULE CONSUMABLES.
- (C) FAILURE OF A SINGLE SEAL HAS NO EFFECT. FAILURE OF THE REDUNDANT (SPACER/RETAINER) SEAL WOULD RESULT IN LOSS OF CREW MODULE CONSUMABLES, HOWEVER, THIS WOULD NOT EXCEED THE MAKEUP CAPABILITY OF THE ARPCS BUT WOULD POSSIBLY RESULT IN EARLY TERMINATION OF MISSION.
- (D) FAILURE OF A SINGLE SEAL HAS NO EFFECT. FAILURE OF THE REDUNDANT (SPACER/RETAINER) SEAL AND AN ADDITIONAL SEAL FAILURE WITHIN THE CREW MODULE COULD RESULT IN A LEAK RATE EXCEEDING THE ARPCS MAKEUP CAPABILIT RESULTING IN LOSS OF CREW/VEHICLE.

REDUNDANCY SCREENS: SEAL FAILS SCREENS "A" AND "B" BECAUSE LEAK TEST OF EACH SEAL INDIVIDUALLY IS NOT FEASIBLE.

# SHUTTLE CRITICAL ITEMS LIST - ORBITER

SUBSYSTEM : CREW MODULE SEALS FMEA NO 01-4 -CS1 -1 REV: 03/29/8

#### DISPOSITION & RATIONALE:

(A) DESIGN (B) TEST (C) INSPECTION (D) FAILURE HISTORY (E) OPERATIONAL USE

## (A) DESIGN

THE PANE ASSEMBLY SEALS ARE REDUNDANT TO THE SPACER/RETAINER SEALS. THESE SEALS PROVIDE INTERFACE SEALING BETWEEN THE PRESSURE PANE, REDUNDANT PANE AND THE WINDOW SPACERS/RETAINERS OF THE WINDOW PANE ASSEMBLY. MULTIPLE SEAL FAILURES ARE NECESSARY BEFORE CREW MODULE ATMOSPHERE LEAKAGE CAN OCCUR, HOWEVER, IF THE SEAL WAS CONSIDERED ABSENTHIS WOULD CAUSE AN EQUIVALENT LEAK HOLE SIZE LESS THAN THE .45 INCH DIAMETER HOLE WHICH THE ARPCS IS CAPABLE OF COMPENSATING AT 8 PSI FOR 1 MINUTES. SEAL MATERIAL (FLUOROCARBON ELASTOMER [VITON]), CHARACTERISTI ARE NOT ADVERSELY AFFECTED BY HUMIDITY, TEMPERATURE, OR PRESSURE EXTREME EXPERIENCED DURING FLIGHT.

#### (B) TEST

QUALIFICATION TESTS: THE FORWARD FUSELAGE, WINDOW BARRIERS, RETAINERS A MOUNTING ASSEMBLIES ARE SUBJECTED, AS A FULL ASSEMBLY, TO PRESSURE, THERMAL AND DEFLECTION LOADING TESTS. (NOTE: INFORMATION AVAILABLE ON TEST IS NOT SPECIFICALLY FOR THE OVERHEAD WINDOW SEALS, HOWEVER, VITON MATERIAL TESTED IS IDENTICAL.)

ACCEPTANCE TESTS: THE CREW MODULE HIGH PRESSURE LEAK TEST PERFORMED AT 14.7 PSID. FINAL ACCEPTANCE TEST IS CONDUCTED AT 3.2 PSID AFTER TRANSF: TO ASSEMBLY AREA AND INSTALLATION OF AVIONICS EQUIPMENT IS COMPLETE. OMRSD: GROUND TURNAROUND INCLUDES PRE-LIFTOFF PRESSURIZATION TEST AT 2 PSID; HOWEVER, IT IS UNLIKELY TO DETECT DUAL SEAL LEAKAGE.

# (c) INSPECTION

# RECEIVING INSPECTION

RECEIVING INSPECTORS CHECK FOR CORRECT IDENTITY AND FOR DAMAGE, VERIFY THAT SUPPLIER SUBMITTED REQUIRED REPORTS, AND VERIFY PARTS ARE PROPERLY PACKAGED TO PREVENT DAMAGE DURING STORAGE.

# CONTAMINATION CONTROL

CLEANLINESS IS MAINTAINED PER MAO110-311. WINDOWS ARE VERIFIED TO BE VISIBLY CLEAN PER MAO110-301 JUST PRIOR TO AND JUST SUBSEQUENT TO ASSEMBLY. INSPECTION VERIFIES, BEFORE INSTALLATION, THAT THE SEALING SURFACE AND VITON SEAL ARE CLEAN, PER MAO106-328 AND VERIFIES CORROSION CONTROL OF METAL PARTS PER MAO106-308.

### ASSEMBLY/INSTALLATION

SEALS ARE INSTALLED PER MAO106-328. PRIOR TO INSTALLATION AN INSPECTION IS PERFORMED TO VERIFY THAT THE SEALING SURFACE AND THE VITON SEAL ARE UNDAMAGED. IT IS ALSO VERIFIED THROUGH INSPECTION THAT THE VITON SEAL SURFACE IS FREE OF DEFECTS, BLEMISHES AND IRREGULARITIES PER DRAWING REQUIREMENTS BEFORE INSTALLATION. ON THE FORWARD WINDOWS, INSPECTION VERIFIES THAT NAS1581C3T17 BOLTS (CLASS 2) ARE INSTALLED PER MAO101-301 AND THAT PROPER TORQUE IS APPLIED.

# SHUTTLE CRITICAL ITEMS LIST - ORBITER

SUBSYSTEM : CREW MODULE SEALS

FMEA NO 01-4 -CS1 -1

REV: 03/29/

TESTING

WINDOW ASSEMBLY IS LEAK TESTED. INSPECTORS VERIFY THAT THE MAXIMUM ALLOWED LEAKAGE OF 0.75 SCIM PER PANE AT A 10 MICRON OR LESS VACUUM LEVEL, IS NOT EXCEEDED.

HANDLING/PACKAGING

THE SUPPLIER PACKAGES DETAIL SEALS PER MK0116-001 REQUIREMENTS AND IDENTIFIES THEM BY PART NUMBER.

(D) FAILURE HISTORY

SIMILAR SILICONE RUBBER AND VITON SEALS USED IN SPACE AND COMMERCIAL APPLICATIONS HAVE NO HISTORY OF LEAKAGE FAILURES. SIMILAR SEALS EXHIBITED NO FLIGHT FAILURES DURING APOLLO CSM PROGRAM.

(E) OPERATIONAL USE

IF INTERFACE LEAKAGE OCCURS, LOSS OF CREW MODULE CONSUMABLES CAN BE MONITORED AND ASSESSED FOR FEASIBILITY OF CONTINUING THE MISSION PER CABIN LEAK PROCEDURES AND FLIGHT RULES.