

System: SRMS

Subsystem: ELECTRICAL SUB-SYSTEM

Assembly Desc: Servo Power Amplifier

Part Number(s): 51140F1177-3      51140F1177-5

Item:

Function: Motor Drive Amplifier Assembly

Provides motor voltage based on demand from tachometer electronics.  
Commutes the motor drive voltage. Provides hardware current limiting, brake drive, direct drive functions and enables backup drive. Provides BITE circuits and BITE verification for MDA.

Failure Mode: MDA +10 V reference out of tolerance.

H/W Func. Screen Failures

Criticality: 2 1R

Mission Phase: Orbit

Cause(s): Motor Drive Amplifier Assembly

MDA +10V reference fails overvoltage.  
MDA +10V reference fails undervoltage.

Failure effect on  
unit/end item:

Erroneous reference voltage to D/A converter, current limiter and current sensors. Hardware current limiting occurs at higher or lower than expected level. The MDA voltage will be higher or lower than commanded. For brakes ON, the motor drive fault detection feedback voltage test will detect. The current sensor zero offset portion of the TCO BITE and the MDA over-current BITE verification may also detect. For brakes OFF or when driving in Direct Drive, the MDA demand voltage BITE may detect. The current summation portion of the TCO BITE may also detect. Possible temporary loss of direct drive.

Worst Case: Unexpected motion. Joint runaway. Autobrakes.

Redundant Paths: Autobrakes (to Safe the System).

Direct Drive (if Available).  
Backup Drive.

**Retention Rationale**

Design:

Comparators and operational amplifiers are standard linear integrated circuits with mature manufacturing technology. Application constraints are in accordance with SPAR-RMS-PA.003.

The SPA board is fabricated using Surface Mount Technology (SMT). This is a PWB assembly technology in which the components are soldered to the solder pads on the surface of the PWB. The significant advantage of this technology is to enable the parts on the board to be more densely packed, to reduce to overall volume and weight of the assembly.

The assembly process is highly automated. The parts are mounted on the boards using a computer controlled "pick and place" machine. The subsequent soldering operation is performed using a belt furnace, in which the time and temperature thermal profile that the PWB assembly is exposed to is tightly controlled and optimized to ensure proper part soldering attachment. The assembly is manufactured under documented procedures and quality controls. These controls are exercised throughout the assembly, inspection and testing of the unit. This inspection includes workmanship, component mounting, soldering, and conformal coating to ensure that it is in accordance with the NHB 5300 standards.

The SMT line used for the SPA PWB assembly has undergone a full qualification program, and assemblies produced on this line are used in other space programs.

The circuit board design has been reviewed to ensure adequate conductor width and separation and to confirm appropriate dimensions of solder pads and component hold provisions. Parts mounting methods are controlled in accordance with MSFC-STD-154A, MSFC-STD-136 and SASD 2573751. These documents require approved mounting methods, stress relief and component security.

Test:

QUALIFICATION TESTS - The SPA is subjected to the following qualification testing:

BRAMPTON ONTARIO L6S4J3

CIL Ref#: 3211

Revision: 0

FMEA Rev: 0

**VIBRATION:** Each axis of the QM is subjected to Flight Acceptance Vibration Test (FAVT), Qualification Acceptance Vibration Test (QA VT) and Qualification Vibration Test (QVT) in accordance with the SPA Vibration Test Procedure (826586). The level and duration for FAVT is as per Figure 6 and Table 2 of 826586; the level and duration for QA VT is as per Figure 7 and Table 2 of 826586; the level and duration for QVT is as per Figure 8 and Table of 826586. At the end of the three successive random vibration test in each axis, both directions (+/-) of each of the axes is subjected to a shock pulse test as per Figure 9 of 826586.

**THERMAL/VACUUM:** QM TVAC Test is in accordance with Figure 5 of the SPA TVAC Test Procedure (826586), with full Functional/Parametric Test performed at levels of +60 degrees C and -36 degrees C, and non-operating at -54 degrees C. The Qualification vacuum levels during TVAC is  $1 \times 10^{-6}$  torr or less. The total test duration is 7 1/2 cycles. The QM SPA is subjected to a minimum of 1000 hours of life testing and 1000 power On-Off cycles.

**EMC:** The QM is subjected to EMC Testing (tests CE01/CE03, CE07, CS01, CS02, CS06, RE02, RS02, and RS03) in accordance with the SPA EMC test Procedure (826477) based on MIL-STD-461A.

**UNIT FLIGHT ACCEPTANCE TESTS** - The FM SPA is subjected to the following acceptance testing:

**VIBRATION:** FM Acceptance Vibration Test (AVT) in accordance with the SPA Vibration Test Procedure (826586), with level and duration as per Figure 6 and Table 2 of 826586.

**THERMAL/VACUUM:** FM TVAC Test is in accordance with Figure 5 of the SPA TVAC Test Procedure (826586), with levels of +49 degrees C and -25 degrees C for a duration of 1 1/2 cycles. The vacuum levels during Acceptance TVAC Test is  $1 \times 10^{-6}$  torr or less.

**JOINT SRU TESTS** - The SPA is tested as part of the joints (ambient and vibration tests only). The ambient ATP for the Shoulder Joint, Elbow Joint, and Wrist Joint are as per ATP.2001, ATP.2003, and ATP.2005 respectively. The vibration test for the Shoulder Joint, and Elbow or Wrist Joint are as per ATP.2002, ATP.2004 and ATP.2006 respectively. Through wire function, continuity and electrical isolation tests are performed per TP.283.

**MECHANICAL ARM REASSEMBLY** - The SPA's/Joints undergo a mechanical arm integration stage where electrical checks are performed per TP.2007.

**MECHANICAL ARM TESTING** - The outgoing split-arm is configured on the Strongback and the Manipulator Arm Checkout is performed per ATP.1932.

**FLIGHT CHECKOUT:** PDRS OPS Checkout (all vehicles) JSC 15987.

#### Inspection:

Units are manufactured under documented quality controls. These controls are exercised throughout design procurement, planning, receiving, processing, fabrication, assembly, testing and shipping of the units. Mandatory inspection points are employed at various stages of fabrication, assembly, and test. Government source inspection is invoked at various control levels.

EEE parts inspection is performed as required by SPAR-RMS-PA.003. Each EEE part is qualified at the part level to the requirements of the applicable specification. All EEE parts are 100% screened and burned-in, as a minimum, as required by SPAR-RMS-PA.003, by the supplier. DPA is performed as required by PA.003 on a randomly selected 5% of parts, maximum 5 pieces, minimum 3 pieces for each lot number/date code of parts received. All cavity devices are subjected to 100% PIND. Wire is procured to specification MIL-W-22759 or MIL-W-31381 and inspected and tested to NASA JSCM8080 Standard Number 95A.

Receiving inspection verifies that all parts received are as identified in the procurement documents, that no physical damage has occurred to parts during shipment, that the receiving documents provide adequate traceability information and screening data clearly identifies acceptable parts.

Parts are inspected throughout manufacture and assembly as appropriate to the manufacturing stage completed. These inspections include:

Printed circuit board inspection for track separation, damage and adequacy of plated through holes, component mounting inspection for correct soldering, wire looping, strapping, etc. Operators and inspectors are trained and certified to NASA NHB 5300.4(3A-1) Standard. Conformal coating inspection for adequate processing is performed using ultraviolet light techniques. P.C. Board Installation Inspection includes checks for correct board installation, alignment of boards, proper connector contact mating, wire routing, strapping of wires etc. Post P.C. Board Installation inspection includes cleanliness and workmanship (Spar/government rep. mandatory inspection point).

Unit Pre-Acceptance Test inspection, which includes an audit of lower tier inspection completion, as built configuration verification to as design etc (mandatory inspection point). A Unit Test Readiness Review (TRR) which includes verification of test personnel, test documents, test equipment calibration/validation status and hardware configuration is convened by QA in conjunction with Engineering, Reliability, Configuration Control, Supplier as applicable, and the government representative, prior to the start of any formal testing (Acceptance or Qualification). Unit level Acceptance Testing (ATP) includes ambient performance, thermal and vibration testing (Spar/government rep. mandatory inspection point).

Integration of unit to Joint SRU - Inspections include grounding checks, connectors for bent or pushback contacts, visual, cleanliness, interconnect wiring and power up test to the appropriate Joint Inspection Test Procedure (ITP). Joint level Pre-Acceptance Test inspection, includes an audit of lower tier inspection completion, as built configuration verification to as design etc. Joint level Acceptance Testing (ATP) includes ambient and vibration testing (Spar/government rep. mandatory inspection point).

Mechanical Arm Reassembly - the integration of mechanical arm subassemblies to form the assembled arm. Inspections are performed at each phase of integration which includes electrical checks, through wiring checks, wiring routing, interface connectors for bent or pushback contacts etc. Mechanical Arm Testing - Strongback and flat floor ambient performance test (Spar/government rep. mandatory inspection point).

**OMRSD Offline:** Power-up arm. Drive each joint in single. Verify no BITE or BITE verification errors. With brakes ON verify no BITE or BITE verification error.

SPAR - BRAMPTON (SSS)  
9445 AIRPORT RD

## Critical Items List

SRMS

BRAMPTON ONTARIO L8S4J3

CIL Ref#: 3211

Revision: 0

FMEA Rev: 0

OMRSD Online: None.  
Installation:

OMRSD Online: Power-up arm. Drive each joint in single. Verify no BITE or BITE verification errors. With brakes ON verify no BITE or BITE verification errors.  
Turnaround:

Screen Failure: A: Pass  
B: Pass  
C: Pass

Crew Training: The crew will be trained to always observe whether the arm is responding properly to commands. If it isn't, apply brakes.

Crew Action: Select Direct Drive if available. If D/O not available select Back-up Drive. Single/Direct Drive switch should be pulsed to maintain proper rates.

Operational Effect: Cannot use Computer Supported modes. Direct Drive may not be available. Autobrakes. Back-up is available. Arm will not stop automatically if failure of the autobrake system has previously occurred. Brakes can be applied manually.

Mission Constraints: Operate under vernier rates within approximately 10 ft of structure. The operator must be able to detect that the arm is responding properly to commands via window and/or CCTV views during all arm operations. Auto trajectories must be designed to come no closer than approximately 5 ft from structure.

### Approvals:

Functional Group	Name	Position	Telephone	Date Signed	Status
Engineer	Hiltz, Michael / SPAR-BRAMPTON	Systems Engineer	4634	06Mar98	Signed
Reliability	Molgaard, Lena / SPAR-BRAMPTON	Reliability Engineer	4680	06Mar98	Signed
Program Management Office	Rice, Craig / SPAR-BRAMPTON	Technical Program Manager	4682	06Mar98	Signed
Subsystem Manager	Glenn, George / JSC-ER	RMS Subsystem Manager	(281) 483-1516	30Mar98	Signed
Technical Manager	Allison, Ron / JSC-MV6	RMS Project Engineer JSC	(713) 483-4072	09Apr98	Signed

SPF Mission Assurance: Caw, David / JSC-NES RMS SYSTEM ENGINEER (281) 483-3999 30 Mar 98 *David C. Caw*