FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL HARDWARE

NUMBER: 02-6-C05 -X

SUBSYSTEM NAME: HYDRAULICS

REVISION: 1

07/24/98

PART DATA

PART NAME VENDOR NAME PART NUMBER
VENDOR NUMBER

LRU

: ACTUATOR, UMBILICAL RÉTRACTOR

MC287-0050

PARKER BERTEA

EXTENDED DESCRIPTION OF PART UNDER ANALYSIS:

ACTUATOR, UMBILICAL RETRACTOR

REFERENCE DESIGNATORS: 50V58AC11

50V58AC12 50V58AC13 50V58AC14 50V58AC15 50V58AC16

QUANTITY OF LIKE ITEMS: 6

THREE ACTUATORS ATTACHED TO EACH OF 2 UMBILICALS

FUNCTION:

THREE ACTUATORS CONNECTED TO EACH ORBITER UMBILICAL HALF PROVIDE MEANS FOR DAMPING OF COMPRESSIVE LOAD DURING RETRACTION OF THE PROPELLANT LINE VALVE CLUSTER INTO THE ORBITER IMMEDIATELY PRIOR TO ORBITER/EXTERNAL TANK SEPARATION. ACTUATOR ASSIST IN RETRACTION DURING FINAL PORTION OF STROKE. EACH ACTUATOR OF EACH UMBILICAL IS POWERED BY A DIFFERENT ONE OF THE THREE HYDRAULIC POWER SYSTEMS.

FAILURE MODES EFFECTS ANALYSIS FMEA -- CIL FAILURE MODE

NUMBER: 02-6-C05-01

REVISION#: 1 07/24/98

SUBSYSTEM NAME: HYDRAULICS

LRU: ACTUATOR, UMBILICAL RETRACTOR.

ITEM NAME: ACTUATOR, UMBILICAL RETRACTOR

CRITICALITY OF THIS

FAILURE MODE: 1R2

FAILURE MODE:

CYLINDER RUPTURE

MISSION PHASE:

LO LIFT-OFF

DO DE-ORBIT

VEHICLE/PAYLOAD/KIT EFFECTIVITY:

102 COLUMBIA

103 DISCOVERY

104 ATLANTIS

105 ENDEAVOUR

CAUSE:

MATERIAL DEFECT

CRITICALITY 1/1 DURING INTACT ABORT ONLY? NO

REDUNDANCY SCREEN

A) PASS

B) PASS

C) PASS

PASS/FAIL RATIONALE:

A)

B)

C)

- FAILURE EFFECTS -

(A) SUBSYSTEM:

LOSS OF ONE OF THREE HYDRAULIC SYSTEMS. LOSS OF VEHICLE'S HYDRAULIC SYSTEM REDUNDANCY. HYDRAULIC SYSTEM ONLY COMMUNICATES WITH ACTUATOR. CYLINDER DURING RETRACTION. LEAKAGE OF HYDRAULIC FLUID THROUGH RUPTURED. CYLINDER COULD NOT OCCUR UNTIL RETRACTION IS INITIATED AT MECO. CYLINDER

FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL FAILURE MODE NUMBER: 02-6-C05- 01

FAILURE WOULD HAVE TO DAMAGE BOTH ISOLATING SOLENOID AND CYLINDER UPON SOLENOID ACTIVATION TO LOSE A HYDRAULIC SYSTEM.

(B) INTERFACING SUBSYSTEM(S):

LOSS OF ONE OF THREE ET UMBILICAL RETRACT ACTUATORS FOR EACH UMBILICAL PLATE. LOSS OF NOSE WHEEL STEERING AND HYDRAULIC LANDING GEAR DEPLOYMENT CAPABILITY IF SYSTEM ONE IS LOST. LOSS OF ONE OF THREE HYDRAULIC POWER SYSTEM TO FLIGHT CONTROL SURFACES AND BRAKES. HYDRAULIC FLUID ON TPS SCREED MAY CAUSE DEGRADED TPS BONDS.

(C) MISSION:

NONE

(D) CREW, VEHICLE, AND ELEMENT(S):

NONE

(E) FUNCTIONAL CRITICALITY EFFECTS:

POSSIBLE LOSS OF CREWVEHICLE WITH TWO FAILURES: THIS FAILURE, PLUS LOSS OF SECOND HYDRAULIC SYSTEM/LOSS OF SECOND UMBILICAL ACTUATOR/LOSS OF PYROTECHNIC BACKUP, IF FIRST FAILURE IS SYSTEM ONE,

-DISPOSITION RATIONALE-

(A) DESIGN:

BURST FACTOR OF 2.5. CYLINDER IS 7075-T73 ALUMINUM WHICH PROVIDES GOOD PHYSICAL PROPERTIES FOR HIGH ALLOWABLE STRESS. ALLOWABLE STRESS IS 40,000 PSI AT 275 DEGREES F. ACTUAL CALCULATED CYLINDER HOOP STRESS (BURST) IS 39,084 PSI. THE MARGIN OF SAFETY IS 0.029. CYLINDER DESIGN AVOIDS STRESS RISERS AND SUDDEN CHANGES IN SECTION IN CRITICAL AREAS.

(B) TEST:

QUALIFICATION:

ENDURANCE CYCLING - 1,500 FULL STROKE CYCLES, 1,000 AT 0 DEGREES F AND 500
AT 160 DEGREES F WITH SIMULATED LOADS AND VELOCITIES APPLIED. PASS/FAIL
CRITERIA: PASSAGE OF SUBSEQUENT PERFORMANCE RECORD TEST

PAGE 4 PRINT DATE: 07/29/98 6-3

FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL FAILURE MODE NUMBER: 02-6-C05- 01

 IMPULSE CYCLING, 50:000 CYCLES, 3:000-4:500-3:000 PSI AT SUPPLY PORT AND 750-1:500-750 PSI AT RETURN PORT. RATE OF 2:0 HZ. PASS/FAIL CRITERIA. PASSAGE OF SUBSEQUENT PERFORMANCE RECORD TEST

- PERFORMANCE RECORD TEST INCLUDES APPLIED FORCE/ACTUATOR PISTON VELOCITY TEST, FREE FLOAT, RETRACT AND EXTEND
- BURST TEST 7,500 PSI AT BOTH PORTS, AT 275 DEG F. PASS/FAIL CRITERIA: NO EVIDENCE OF EXTERNAL LEAKAGE OR RUPTURE
- RUPTURE TEST INCREASE TO RUPTURE OR 125 PERCENT OF BURST PRESSURE (7,500 PSi)

ACCEPTANCE:

- EXAMINATION OF PRODUCT WEIGHT, WORKMANSHIP FINISH, DIMENSIONS, AND CONSTRUCTION
- PROOF PRESSURE 4,500 PSI FOR TWO MINUTES AT 275 DEG F AND REPEATED AT AMBIENT TEMPERATURE AT BOTH PORTS FOR TWO CYCLES EACH, PASS/FAIL CRITERIA: NO EXTERNAL LEAKAGE OR PERMANENT DEFORMATION.
- PERFORMANCE RECORD TEST INCLUDES APPLIED FORCE/ACTUATOR PISTON VELOCITY TEST, FREE FLOAT, RETRACT AND EXTEND.

GROUND TURNAROUND TEST

ANY TURNAROUND CHECKOUT TESTING IS ACCOMPLISHED IN ACCORDANCE WITH OMRSD.

(C) INSPECTION:

RECEIVING INSPECTION

RECORDS AND TEST REPORTS ARE MAINTAINED CERTIFYING MATERIAL AND PHYSICAL PROPERTIES (RAW MATERIAL, ANNEALING, AND ULTRASONIC INSPECTION).

CONTAMINATION CONTROL

CLEANLINESS LEVEL OF 190 PER MAO110-301 IS VERIFIED BY INSPECTION.

CRITICAL PROCESSES

HEAT TREATMENT AND ANODIZATION PROCESSES ARE VERIFIED BY INSPECTION.

NDE

PENETRANT PROCESS IS VERIFIED BY INSPECTION.

ASSEMBLY/INSTALLATION

EXAMINATION TESTS PERFORMED TO VERIFY THAT ALL QUALITY ASSURANCE DOCUMENTATION IS COMPLETE, VISUALLY INSPECT ASSEMBLY TO ASSURE COMPLIANCE WITH 261600 DRAWING, AND VERIFY THAT NO OBVIOUS DEFECTS ARE EVIDENT. FINAL INSPECTION OF ALL DIMENSIONS IS PERFORMED. MANIFOLD BLANK IS INSPECTED TO LAYOUT PATTERN AND DRAWING. MANIFOLD IS NUMERICAL CONTROL MACHINE INSPECTED TO DRAWING PRIOR TO ANODIZE (THREADS ARE INSPECTED). CYLINDER HONED TO DETAILED INSTRUCTIONS ON OPERATIONS SHEETS AND VERIFIED BY INSPECTION. STRICT COMPLIANCE WITH MACHINING SPECIFICATION (BMF 5115) AND CORROSION CONTROL PLAN (BMF 5110) REQUIRED AND VERIFIED BY INSPECTION.

TESTING

ATP IS VERIFIED BY INSPECTION.

PAGE: 5 PRINT DATE: 07/29/98 64

FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL FAILURE MODE NUMBER: 02-6-C05- 01

HANDLING/PACKAGING INSPECTION VERIFIES PACKAGING PRIOR TO SHIPMENT.

(D) FAILURE HISTORY:

CURRENT DATA ON TEST FAILURES. FLIGHT FAILURES, UNEXPLAINED ANOMALIES, AND OTHER FAILURES EXPERIENCED DURING GROUND PROCESSING ACTIVITY CAN BE FOUND IN THE PRACA DATA BASE.

(E) OPERATIONAL USE:

NONE, RAPID LEAK WOULD DEPLETE HYDRAULIC SYSTEM BEFORE ACTION COULD BE TAKEN.

| - APPROVALS - | | |
|-----------------------------------------|------------------------------|-----------------|
| EDITORIALLY APPROVED TECHNICAL APPROVAL | · BNA · VIA APPROVAL FORM | 95-CIL-009 02-6 |