# SHUTTLE CRITICAL ITEMS LIST - ORBITER

SUBSYSTEM : AUXILIARY POWER (APUS) FMEA NO 04-2 -CONTL6-1 REV:02/26/8

VEHICLE

ASSEMBLY :APU CONTROLLER P/N RI :MC201-0001-0065

CRIT. FUNC: 1R CRIT. HCW:

P/N VENDOR:SS P/N 729485C

102 103 104

QUANTITY : 3

EFFECTIVITY: X X X

:ONE PER APU

PHASE(S): PL IΔ 00 X DO X LS

REDUNDANCY SCREEN: APPROVED BY

A-PASS B-FAIL C-PAS: APPROVED BY (NASA):

PREPARED BY: DES

R STEDMAN DES \$5M

REL QΕ

T R BOLTZIGBREL W J SMITH QΕ

REL Æ

ITEM:

LUBE OIL REPRESSURIZATION CIRCUIT

### FUNCTION:

(1) PROVIDES SIGNAL TO OPERATE GN2 SOLENOID VALVE WHEN THE LUBE OIL CAS: PRESSURE (V46P0151A) IS BETWEEN 5.5 +/- 1.5 AND 8.5 +/- 1.5 PSIA.

### FAILURE HODE:

LOSS OF OUTPUT, ERRONEOUS OUTPUT.

## CAUSE(S):

CONTROLLER INTERNAL PIECE PART FAILURE, EMI, OPEN OR SHORT CIRCUIT.

### EFFECT(\$) ON:

- (A)SUBSYSTEM (B)INTERFACES (C)MISSION (D)CREW/VEHICLE
- (A) NO EFFECT UNLESS GEARBOX PRESSURE HAS DECAYED BELOW 4 PSIA. PRESSURE HAS DECAYED, AFU MAY NOT RESTART. THIS FAILURE WOULD NOT BE DETECTABLE IN FLIGHT UNLESS REPRESSURIZATION OF THE GEARBOX WAS REQUIRED
- (B) IF GEARBOX PRESSURE IS LOW, LOSS OF ONE HYDRAULIC SYSTEM FOR ENTRY.
- (C) NONE.
- (0) NO EFFECT UNTIL SECOND SYSTEM LOST.
- (E) FUNCTIONAL CRITICALITY EFFECT LOSS OF CREW/VEHICLE IF GEARBOX PRESSURE DECAYS BELOW 4.5 PSIA, REPRESSURIZATION CIRCUIT FAILS, AND LOSS OF SECOND APU OCCURS. NOT DETECTABLE IN FLIGHT BECAUSE OTHER CAUSES OF LOSS OF REPRESSIZATION EXIST (REF 04-2-LV14-2 - REPRESS VALVE FAILED CLOSED, 04-2-MD19-2 - LOSS OF GN2 THROUGH FILL QD).

## DISPOSITION & RATIONALE:

(A)DESIGN (B)TEST (C)INSPECTION (D)FAILURE HISTORY (E)OPERATIONAL USE

### (A) DESIGN

ELECTRICAL COMPONENTS ARE REQUIRED TO BE QUALIFIED, PROPERLY DERATED AND APPLIED PER MCZ01-0001, PARAGRAPH 3.3.2.2. MECHANICAL PARTS SELECTED FROM MF0004-100. ELECTRICAL PARTS SELECTED FROM MF0004-400. CONFORMAL COATING PER SUNDSTRAND SPEC CP 17.32-01. CLEANLINESS PER MA0110-301. CONTROLLER VIBRATION DAMPED AT MOUNTING.

### SHUTTLE CRITICAL ITEMS LIST - ORBITER

SUBSYSTEM : AUXILIARY POWER (APUS) FMEA NO 04-2 -CONTL6-1 REV: 02/26/88

THE OPPL CALLS FOR GLASSIVATION FOR INTEGRATED CIRCUIT DIE, SINGLE SEAL FOR TANTALUM WET SLUG CAPACITORS, ETC. DERATING OF ELE PARTS IS EXPANCED BEYOND THE SIMPLISTIC (75% X RATED) REQUIREMENTS OF THE CONTRACT.

## (B) TEST

CONTROLLER IS FUNCTIONALLY TESTED DURING ATP. CONTROLLER IS SUBJECTED TO AVT. CONTROLLER IS THERMAL TESTED DURING ATP - RANGE 70 DEG F, 130 DEG F, 30 DEG F.

CONTROLLER IS QUALIFIED FOR QAVT, EMI, THERMAL VACUUM (-65 DEG F TO 165 DEG F, 80 K FT FOR 10 CYCLES). ADDITIONAL HUMIDITY, FLIGHT VIBRATION, AND THERMAL VACUUM TESTS ARE CONDUCTED FOR THE OPERATIONAL CONFIGURATION.

ALL FEE PARTS ARE SUBJECTED TO SCREENING AND BURN-IN TESTS TO DETECT MARGINAL PARTS AND TO INDUCE INFANT MORTALITY FAILURES.

OMRSD: LPS AUTO BITE TEST IS PERFORMED ON EACH APU EVERY FLOW.

## (C) INSPECTION

#### RECEIVING INSPECTION

VISUAL AND DIMENSIONAL INSPECTIONS ARE PERFORMED ON ALL INCOMING PARTS. MATERIAL AND PROCESSES CERTIFICATIONS ARE VERIFIED.

### CONTAMINATION CONTROL

CLEANLINESS IS VERIFIED BY INSPECTION.

#### ASSEMBLY/INSTALLATION

MANUFACTURING, ASSEMBLY, AND INSTALLATION REQUIREMENTS ARE VERIFIED BY INSPECTION.

#### CRITICAL PROCESSES

SOLDERING TO NHB 5300.4(3A) IS VERIFIED BY INSPECTION.

### **TESTING**

TEST EQUIPMENT AND TOOL CALIBRATION ARE VERIFIED BY INSPECTION. ATP IS WITNESSED AND VERIFIED BY INSPECTION.

#### HANDLING/PACKAGING

HANDLING, PACKAGING, STORAGE, AND SHIPPING PROCEDURES ARE VERIFIED BY INSPECTION.

#### (D) FAILURE HISTORY

NO FLIGHT FAILURES TO DATE. SANGAMO CAPACITORS FAILED IN ATP, RESULTING IN ALL CAPACITORS BEING CHANGED OUT (CAR AC9235).

ALTERNATE WAS PART SUBSTITUTED IN CONTROLLER, RESULTING IN ERRATIC OUTPUT DURING VEHICLE CHECKOUT (CAR AC2853). CIRCUIT WAS REDESIGNED TO BE IMMUNE TO COMPONENT MANUFACTURING VARIATIONS.

### (E) OPERATIONAL USE

ATTEMPT TO START/RUN WITH LOW GEARBOX PRESSURE.