8PAR - BRAMPTON (SSS)

9445 AIRPORT RD

Critical Items List

8RMS

CIL Ref#: 3092

Revision: 0

FMEA Rev: 0

BRAMPTON ONTARIO L684J3

System: SRMS

Subsystem: ELECTRICAL SUB-SYSTEM

Assembly Desc: Servo Power Amplifier

Part Number(s): 51140F1177-3

\$1140F1177-5

Hem:

Function: Motor Drive Amplifier Assembly

Provides motor voltage based on demand from tachometer electronics.

Commutates the motor drive voltage. Provides hardware outrent limiting, brake drive, direct drive functions and enables backup drive. Provides BITE circuits and

BITE verification for MDA.

Failure Mode: Brake failed ON in Computer Supported and Direct Drive modes.

HWV Func. Screen Failures

Criticality: 2

2 1

Mission Phase: Orbit

Cause(s): Motor Drive Amplifier Assembly

Brake permanently ON in computer supported and direct modes.

Failure effect on unit/end item:

Brake will come on for failed joint. Brake 8/TE will detect and apply MCIU autobrakes on remaining joints. In direct drive joint motor may be

able to overdrive brake.

Worst Case: Unexpected motion. Frozen joint. Autobrakes.

edundard Paths: Autobrakes (to Safe the System).

Direct Drive (If Available).

Backup Drive.

etention Rationale

Design:

Resistors and capacitors used in the design are selected from established reliability (ER) types. Ufe expectancy is increased by ensuring that all allowable stress levels are derated in accordance with SPAR-RMS-PA.003. All ceramic and electrolytic capacitors are northerly subjected to radiographic inspection in accordance with the requirements of MSFC-8TD-356.

The SPA board is fabricated using Surface Mount Technology (SMT). This is a PWB assembly technology in which the components are soldered to the solder pade on the surface of the PWB. The significant advantage of this technology is to enable the parts on the board to be more densely packed, to reduce to overall volume and weight of the assembly.

The assembly process is highly automated. The parts are mounted on the boards using a computer controlled "pick and place" machine. The subsequent soldering operation is performed using a best furnace, in which the time and temperature thermal profite that the PWB assembly is exposed to is tightly controlled and optimized to ensure proper part soldering attachment. The assembly is manufactured under documented procedures and quality controls. These controls are exercised throughout the essembly, inspection, and testing of the unit. This inspection includes workmanship, component mounting, acidering, and conformal coating to ensure that it is in accordance with the NHB 5300 standards.

The SMT line used for the SPA PWB assembly has undergone a full qualification program, and assembles produced on this line are used in other space programs.

The circuit board design has been reviewed to ensure adequate conductor width and separation and to confirm appropriate dimensions of scaler pads and of component hold provisions. Parts mounting methods are controlled in accordance with MSFC-STD-154A, MSFC-STD-138 and SASD 2573751. These obcurrents require approved mounting methods, stress relief and component security.

Test:

QUALIFICATION TESTS - The SPA is subjected to the following qualification testing:

VIBRATION: Each axis of the QM is subjected to Flight Acceptance Vibration Test (FAVT), Qualification Acceptance Vibration Test (QAVT), and Qualification Vibration Tests (QVT) in accordance with the SPA Vibration Test Procedure (825585), The level and duration for FAVT is as per Figure 6 and Table 2 of 826588; the level and duration for QAVT is as per Figure 7 and Table 2 of 826588; the level and duration for QAVT is

spared: 16Sep96 by Fung, Bill

Supersedes: N/A

Critical Items List

SR

BRAMPTON ONTARIO LOSAJ3

CIL Ref#: 3092

Revision: 0

FMEA Rev: 0

as per Figure 8 and Table of 826586. At the end of the three successive random vibration test in each axis, both directions (+/-) of each 6 axis is subjected to a shock pulse test as per Figure 9 of 826586.

THERMAL/VACUUM: QM TVAC Test is in accordance with Figure 5 of the SPA TVAC Test Procedure (826588), with full Functional/Parametrio Test performed at levels of +60 degrees C and -36 degrees C, and non-operating at -54 degrees C. The Qualification vacuum levels during TVAC is 1X10**-6 for or less. The total test duration is 7 1/2 cycles. The QM SPA is subjected to a minimum of 1000 hours of life testing and 1000 power On-Off cycles.

EMC: The QM is subjected to EMC Testing (tests CE01/CE03, CE07, CS01, CS02, CS06, RE02, RS02, and RS03) in accordance with the SPA EMC test Procedure (826477) based on MIL-STD-461A.

UNIT FLIGHT ACCEPTANCE TESTS - The FM SPA is subjected to the following acceptance testing:

VIBRATION: FM Acceptance Vibration Test (AVT) in accordance with the SPA Vibration Test Procedure (826586), with level and duration a per Figure 6 and Table 2 of 826586.

THERMAL/VACUUM: FM TVAC Test is in accordance with Figure 6 of the SPA TVAC Test Procedure (826585), with levels of +49 degrees and -25 degrees C for a duration of 1 1/2 cycles. The vacuum levels during Acceptance TVAC Test is 1X10**-5 for or less.

JOINT SRU TESTS - The SPA is tested as part of the joints (ambient and vibration tests only). The ambient ATP for the Shoulder Joint, Elbow Joint, and Wrist Joint are as per ATP.2001, ATP.2003, and ATP.2006 respectively. The vibration test for the Shoulder Joint, and Elbo or Wrist Joint are as per ATP.2002, ATP.2004 and ATP.2006 respectively. Through wire function, continuity and electrical isolation tests are performed per TP.283.

MECHANICAL ARM REASSEMBLY - The SPA's/Jeints undergo a mechanical arm integration stage where electrical checks are performs per TP.2007.

MECHANICAL ARM TESTING - The outgoing split-arm is configured on the Strongback and the Manipulator Arm Checkout is performed per ATP.1932.

FLIGHT CHECKOUT: PORS OPS Checkout (all vehicles) JSC 16987.

Inspection:

Units are manufactured under documented quality controls. These controls are exercised throughout design procurement, planning, receiving, processing, fabrication, assembly, testing and shipping of the units. Manufactory inspection points are employed at various stages of fabrication, assembly, and test. Government source inspection is invoked at various control levels.

EEE parts inspection is performed as required by SPAR-RMS-PA.003. Each EEE part is qualified at the part level to the requirements (applicable specification. All EEE parts are 100% screened and burned-in, as a minimum, as required by SPAR-RMS-PA.003, by the supplier. DPA is performed as required by PA.003 on a randomly selected 5% of parts, maximum 5 pieces, minimum 3 pieces for each lot number/date code of parts received. All cavity devices are subjected to 100% PIND. Wire is produced to specification MIL-W-22759 or MiL-W-81381 and inspected and tested to NASA JSCM8060 Standard Number 95A.

Receiving inspection verifies that all parts received are as identified in the procurement documents, that no physical damage has occurred to parts during shipment, that the receiving documents provide adequate traceability information and screening data clearly identifies acceptable parts.

Parts are inspected throughout manufacture and assembly as appropriate to the manufacturing stage completed. These inspections include: Printed circuit board inspection for track separation, damage and adequacy of plated through holes, component mounting inspection for correct soldering, whre looping, strapping, etc. Operators and inspectors are trained and certified to NASA NHB 5300.4(3A-1) Standard. Conformal coating inspection for adequate processing is performed using ultraviolat light techniques. P.C. Board installation inspection include checks for correct board installation, alignment of boards, proper connector contact mating, wire routing, strapping of wires etc. Post P.C. Board installation inspection includes cleanliness and workmentable (Spar/government rep. mandatory inspection point).

Unit Pre-Acceptance Test inspection, which includes an audit of lower tier inspection completion, as built configuration vertilication to as design etc (mandatory inspection point). A unit Test Readiness Review (TRR) which includes verification of test personnel, test documents, test equipment calibration/validation status and hardware configuration is convened by QA in conjunction with Engineering, Reliability, Configuration Control, Supplier as applicable, and the government representative, prior to the start of any formal testing (Acceptance or Qualification). Unit level Acceptance Testing (ATP) includes ambient performance, thermal and vibration testing (Spar/government rep. mandatory inspection point).

Integration of unit to Joint SRU - Inspections include grounding checks, connectors for bent or pushback contracts, visual, cleanliness, interconnect wiring and power up test to the appropriate Joint Inspection Test Precadure (ITP). Joint level Pre-Acceptance Test Inspection, includes an audit of Inwer tier inspection completion, as built configuration verification to as design etc. Joint level Acceptance Testing (ATP) includes ambient and vibration testing (Spar/government rep. mandatory Inspection point).

Mechanical Arm Ressembly - the integration of mechanical arm subaspernibles to form the assembled arm. Inspections are performed at each phase of integration which includes electrical checks, through wiring checks, wiring routing, interface connectors for bent or pushback contacts etc. Mechanical Arm Testing - Strongback and flat floor ambient performance test (Spar/government rep. mandatory inspection point).

OMRSD Offline: Power-up arm. Select Computer Supported and Direct Drive modes and verify no Brake BITE errors,

OMRSD Online None.

Installation:

OMRSD Online Power-up arm. Select Computer Supported and Direct Drive modes and verify no Brake BITE errors.

Turnaround:

Prepared:

189ep96 by Fung. Bill

Supersedes: N/A

SPAR - BRAMPTON (SSS)

9445 AIRPORT RD

Critical Items List

SRMS

CIL Ref#: 3092

Revision: 0

FMEA Rev: 0

BRAMPTON ONTARIO L6S4J3

Screen Failure: A: Pass

B: Pass

C: Pass

Crew Training: The crew will be trained to always observe whether the arm is responding properly to commands. If it isn't, apply brakes.

Crew Action: Select Direct Drive if evailable. If D/D not available select Back-up Orive. Single/Direct Drive switch should be pulsed to maintain proper rates.

Operational Effect: Cannot use Computer Supported modes. Direct Drive may not be available. Autobrakes. Back-up is available. Arm will not stop automatically if failure of the autobraice system has previously occurred. Brakes can be applied mainually. Override capability exects for computer supported

modes,

Mission. Operate under vernier rates within approximately 10 ft of structure. The operator must be able to detect that the arm is responding properly to Constraints: commands via window and/or CCTV views during all arm operations. Auto trajectories must be designed to come no closer than approximately

5 ft from structure.

unctional Group	Name	Position	Telephone	Date Signed	Startus
ngineer	Hitz. Michael / SPAR-BRAMPTON	Systems Engineer	4834	OSMar96	Signed
eliability	Molgaard, Lena / SPAR-BRAMPTON	Reliability Engineer	4590	06Mar98	Signed
ogram Management Offic	Rice, Craig / SPAR-BRAMPTON	Technical Program Menager	4892	06Mar98	Signed
bsystem Manager	Glenn, George / JSC-ER	RMS Subsystem Manager	(281) 453-1516	30Mar98	Signed
chnical Manager	Allison, Ron / JSC-MVB	RMS Project Engineer JSC	(713) 483-4072	09Apr98	Signed