

SHUTTLE CRITICAL ITEMS LIST - ORBITER

SUBSYSTEM : ACTIVE THERMAL CONTROL FMEA NO 06-3C -0104 -3 REV:08/29/
ASSEMBLY : FREON THERMAL LOOP CRIT. FUNC: :
P/N RI : MC250-0001-0025 CRIT. HDW: :
P/N VENDOR: SV755511 VEHICLE 102 103 104
QUANTITY : 1 EFFECTIVITY: X X X
: ONE/VEHICLE PHASE(S): PL '0 X 00 X 00 X 15
:

PREPARED BY: DES O. TRAN *O. Tran* APPROVED BY: REDUNDANCY SCREEN: A-PASS B-PASS C-PAS
REL D. RISING *D. Rising* DES *[Signature]* APPROVED BY (NASA):
QE W. SMITH *W. Smith* REL *[Signature]* SSM *[Signature]*
QE *[Signature]* REL *[Signature]* QE *[Signature]*

ITEM:
HEAT EXCHANGER, GSE.

FUNCTION:
THE GSE HEAT EXCHANGER TRANSFERS ORBITER WASTE HEAT VIA FREON COOLANT LOOPS TO GROUND SUPPORT EQUIPMENT DURING GROUND TURNAROUND. THE HEAT EXCHANGER WAS DESIGNED WITH REDUNDANT GSE LOOPS. THE REDUNDANT GSE LOOP IS CAPPED AND NOT IN USE.

FAILURE MODE:
INTERNAL LEAKAGE, FREON 21 TO GSE FREON 114.

CAUSE(S):
CORROSION, VIBRATION, MECHANICAL SECON.

EFFECT(S) ON:
(A) SUBSYSTEM (B) INTERFACES (C) MISSION (D) CREW/VEHICLE
(A) LOSS OF FREON FROM ONE FREON COOLANT LOOP THROUGH THE GSE CONNECTOR RELIEF VALVE.
(B) POSSIBLE LOSS OF ONE FREON COOLANT LOOP FOR VEHICLE COOLING.
(C) POSSIBLE LOSS OF MISSION. EARLY MISSION TERMINATION FOR LOSS OF COOLANT LOOP.
(D) SECOND ASSOCIATED FAILURE (LOSS OF REDUNDANT FREON COOLANT LOOP) WILL CAUSE LOSS OF ALL VEHICLE COOLING AND MAY RESULT IN LOSS OF CREW/VEHICLE

SHUTTLE CRITICAL ITEMS LIST - ORBITER

SUBSYSTEM : ACTIVE THERMAL CONTROL FMEA NO 06-3C -0304 -1 REV: 08/79/3

DISPOSITION & RATIONALE:

(A) DESIGN (B) TEST (C) INSPECTION (D) FAILURE HISTORY (E) OPERATIONAL USE

(A) DESIGN

THE HEAT EXCHANGER IS MADE FROM STAINLESS STEEL AND NICKEL BRONZE ALLOYS, WHICH ARE CORROSION RESISTANT AND COMPATIBLE WITH FREON 21 AND FREON 114, AND CONTAINS NO MOVING PARTS SUBJECT TO WEAR. THE FLOW HEADERS ARE MACHINED FROM A SINGLE PIECE STAINLESS STEEL BAR. THE HEADERS ARE WELDED TO THE CORE, WHICH IS MADE OF 136 STACKED PLATE-FIN STAINLESS STEEL PARTING SHEETS (THICKNESS = 0.005 INCH). DESIGN PROOF PRESSURE IS 1.5 AND BURST PRESSURE IS 2.0 TIMES MAXIMUM OPERATING PRESSURE.

(B) TEST

QUALIFICATION TEST - QUALIFICATION TESTED FOR 100 MISSION LIFE. THE HEAT EXCHANGER WAS SUBJECTED TO A PROOF/RUPTURE TEST FOR QUALIFICATION. DESIGN PROOF IS 575 PSIG AND UNIT DID NOT RUPTURE UNTIL 2440 PSIG $\frac{1}{2}$ (MAXIMUM GSE FREON 114 OPERATING PRESSURE IS 250 PSIG). VIBRATION TESTS AT 0.075 G²/HZ FOR 52 MIN/AXIS, SHOCK TESTED AT +/- 20 G EACH AXIS.

ACCEPTANCE TEST - CORE IS LEAK TESTED PRIOR TO INSTALLING THE HEADERS AND AGAIN IN ATP.

ORSD - PCL'S ARE LEAK CHECKED PRIOR TO EACH FLIGHT. CONTINUOUS MONITORING OF THE FREON ACCUMULATOR QUANTITY WILL DETECT THIS LEAK. FREON CHEMICAL ANALYSIS PER SE-S-0073 DURING SERVICING.

(C) INSPECTION

RECEIVING INSPECTION

RAW MATERIAL AND PURCHASED COMPONENTS REQUIREMENTS ARE VERIFIED BY INSPECTION. PARTS PROTECTION IS VERIFIED BY INSPECTION.

CONTAMINATION CONTROL

SYSTEMS FLUID ANALYSES FOR CONTAMINATION ARE VERIFIED BY INSPECTION. CONTAMINATION CONTROL PLAN IS VERIFIED BY INSPECTION. CONTAMINATION CONTROL PROCESSES AND CLEAN AREAS ARE VERIFIED BY INSPECTION.

ASSEMBLY/INSTALLATION

MANUFACTURING, INSTALLATION, AND ASSEMBLY OPERATIONS ARE VERIFIED BY INSPECTION. SHEET METAL PARTS ARE INSPECTED AND VERIFIED BY INSPECTION. SURFACE FINISHES VERIFIED BY INSPECTION. DIMENSIONS VERIFIED BY INSPECTION.

CRITICAL PROCESSES

WELDING IS VERIFIED BY INSPECTION. ALL WELDS ARE STRESS RELIEVED AFTER WELDING, VERIFIED BY INSPECTION. BRAZING IS VERIFIED BY INSPECTION.

SHUTTLE CRITICAL ITEMS LIST - ORBITER

SUBSYSTEM : ACTIVE THERMAL CONTROL FMEA NO 06-3C -0304 -3 REV:08/89

NONDESTRUCTIVE EVALUATION

HEADER WELDS TO THE TUBES ARE PENETRANT AND X-RAY INSPECTED. OTHER WELDS (MOUNTING PADS AND HEADER WELDS TO THE CORES) ARE PENETRANT AND 10X MAGNIFICATION VISUALLY INSPECTED. BRAZES ARE VERIFIED BY PROOF AND LEAK TESTS.

TESTING

INSPECTION VERIFIES THAT RESULTS OF ACCEPTANCE TESTING AND FLOWRATES ARE WITHIN SPECIFIED LIMITS.

HANDLING/PACKAGING

HANDLING AND PACKAGING REQUIREMENTS VERIFIED BY INSPECTION.

(D) FAILURE HISTORY

NO FAILURE HISTORY.

(E) OPERATIONAL USE

ON-BOARD ALARM, FREON INLET PRESSURE, WILL PROVIDE INDICATION OF HARDWARE FAILURE. FREON PUMP WILL BE TURNED OFF AND LOSS OF ONE FREON LOOP POWERDOWN WILL BE PERFORMED. ENTRY AT NEXT PRIMARY LANDING SITE.